

NOTE: AERIAL PHOTO, PARCEL LINES AND TOPOGRAPHIC INFORMATION PROVIDED BY CITY OF FRANKLIN G.I.S.

TREE CANOPY RETENTION

EA	EXISTING	REMOVED	RETAINED
	30,162 SF	9,791 SF	20,371 SF
	8,528 SF	3,558 SF	4,970 SF
	8,287 SF	8,287 SF	0 SF
	5,166 SF	2,311 SF	2,855 SF
=	52,143 SF	23,947 SF	28,196 SF
NOPY DATA			
TREE CANOPY: 52,143 SF 52,143 SF/301,423 SF = .173 (17.3%) OF TOTAL SITE			
D CANOPY PRESERVATION = 54% OF TOTAL CANOPY 52,143 SF * 54% = 28,157 SF			
D CANOPY PRESERVED = 28,196 SF (54%) OF TOTAL EXISTING CANOPY			

SPECIMEN TREE: > 24"

HYDRANT LOCATED AT THE INTERSECTION OF CARLISLE LANE AND OLD CHARLOTTE PIKE. 2,771 PSI AT 20 GPM

DUE TO EXISTING CONDITIONS OF THIS PROPERTY, AND ADJACENT EXISTING SUBDIVISION, OFF-SITE CONNECTIONS ARE NOT POSSIBLE AND ARE NOT PROVIDED WITH THIS PUD. A SPECIAL EXCEPTION IS REQUESTED FROM THE ENGINEERING DEPARTMENT FOR OFF SITE

LOTS 2, 17, 19, AND 20 ARE CRITICAL TREE LOTS.

CARDEL VILLAGE IS LOCATED IN THE WEST HARPETH CHARACTER AREA. THE DESIGN STANDARDS PERMIT EITHER TRADITIONAL OF CONVENTIONAL DEVELOPMENT FORMS. SINGLE FAMILY DETACHED HOMES ARE PERMITTED WITHIN THIS CHARACTER AREA AT DENSITIES SIMILAR TO THE THE EXISTING DEVELOPED SUBDIVISIONS.

WHCO-2

APPLICABLE DEVELOPMENT STANDARD: CONVENTIONAL 1. THE EXISTING USES WITHIN THE WEST HARPETH CHARACTER AREA

2 ARE PREDOMINANTLY SINGLE FAMILY DETACHED HOMES. THE PROPOSED PLAN PROVIDES SINGLE FAMILY HOME LOTS.

2. THE PROPOSED DEVELOPMENT PLAN FACES FUTURE HOMES TOWARD CARLISLE LANE, FRONTING THE STREET, WITH ALLEY


3. THE PROPOSED DEVELOPMENT WILL BE ACCESSED FROM CARLISLE

CARDEL VILLAGE IS LOCATED IN THE WHCO-2 CHARACTER AREA. THE DESIGN STANDARDS PERMIT EITHER TRADITIONAL OF CONVENTIONAL DEVELOPMENT FORMS. SINGLE FAMILY DETACHED HOMES ARE PERMITTED WITHIN THIS CHARACTER AREA AT DENSITIES SIMILAR TO THE THE EXISTING DEVELOPED SUBDIVISIONS.

CARDEL VILLAGE IS A 20 LOT SINGLE FAMILY DETACHED RESIDENTIAL SUBDIVISION ACCESSED FROM CARLISLE LANE. THE PROPOSED RESIDENTIAL LOTS ARE CONSISTENT WITH THE LOTS OF BLOSSOM PARK TO THE EAST, AND CORNERSTONE TO THE SOUTH. OPEN SPACE AND A TRANSITIONAL FEATURES BUFFER HAS BEEN PLACED ON THE NORTHERN BOUNDARY OF THE SUBDIVISION ADJACENT TO THE NEIGHBORING ESTATE RESIDENTIAL PROPERTY.

THE PROPOSED PLAN INCORPORATES THE FUTURE RIGHT-OF-WAY OF CARLISLE LANE PER THE MAJOR THOROUGHFARE PLAN. RIGHT-OF-WAY WILL BE DEDICATED TO THE CITY OF FRANKLIN FOR THESE FUTURE IMPROVEMENTS. AN ALLEY IS PROPOSED BEHIND LOTS 17 TO 20 SO THAT THESE HOMES MAY FRONT ONTO CARLISLE LANE AND SO THAT IN THE FUTURE THE ALLEY MAY BE EXTENDED TO THE NORTH PARALLEL TO CARLISLE LANE.

PHASING THE DEVELOPMENT WILL BE CONSTRUCTED AS A SINGLE PHASE. HILLSIDE PROTECTION OVERLAY BUFFER. LOTS 1, 2, 3, 4, 16, 17, 18, 19, AND 20 ARE LOCATED WITHIN THE BUFFER



PER HOME: 20 x .64 = 12.8 STUDENTS WALNUT GROVE ELEMENTARY SCHOOL 3.4 MILES GRASSLAND MIDDLE SCHOOL 6.1 MILES FRANKLIN HIGH SCHOOL 2.5 MILES

REFUSE COLLECTION REFUSE COLLECTION SERVICE WILL BE PROVIDED BY THE CITY OF FRANKLIN SOLID WASTE.

RESTRICTIVE COVENANTS A HOME OWNER'S ASSOCIATION WILL BE ESTABLISHED PRIOR TO THE FIRST OCCUPANCY OF RESIDENTS. THE HOME OWNER'S ASSOCIATION WILL REGULATE ARCHITECTURAL STANDARDS AND THE MAINTENANCE OF THE COMMUNITY. THE HOA WILL MAINTAIN ALL COMMON OPEN SPACE AND RECREATIONAL AREAS.

MINERAL RIGHTS NO THIRD PARTY MINERAL RIGHTS ARE ASSOCIATED WITH THIS PROPERTY. COF 5916

а

PLAN

.0