

G and G Lawncare LLC
P. O. Box 176
Spring Hill, TN 37174
(931)797-1830
gandglawncare@charter.net



ESTIMATE

ESTIMATE # 1479
DATE 03/22/2018

ADDRESS
City of Franklin

Please detach top portion and return with your payment.

ACTIVITY	QTY	RATE	AMOUNT
Labor Spencer Creek Rd: Retaining wall repair Excavate 300ft of roadway ditch to utility poles Haul off all debris Install 30in high natural stone retaining wall using existing stone on site All excess stone will be removed and hauled off Gravel backfill of retaining wall 18in in depth 18in of dirt backfill 1- 4in ADS French drain pipe behind wall, day lighted at one end Stone wall to be set on compacted gravel base footer Retaining wall to have dry stack look on one exterior face and top Labor, excavation, haul off, footers, and masonry materials included in price	1	48,500.00	48,500.00

TOTAL **\$48,500.00**

Accepted By

Accepted Date