FINAL PLAT FORREST CROSSING SUBDIVISION

SECTION ONE, REVISION ELEVEN

Consolidation of Plat of Lots 1286, 1287, 1288, 1289, 1290, & 1291

RACHEL SPRINGS BUSINESS VILLAGE FRANKLIN, WILLIAMSON COUNTY, TENNESSEE

General Notes

- 1. The purpose of this plat revision is to consolidate Lot 1286 through Lot 1291 into one buildable lot, and create, modify, and abandon easements and revise the common access easement.
- 2. Bearings are based on the Tennessee State Plane Coordinate System of 1983.
- 3. All distances were measured with E.D.M. equipment and have been adjusted for temperature.
- 4. Being Parcels 1.07, 1.08. 1.09, 1.10, 1.11 and 1.12 on Williamson County Property Map 79P,
- 5. This Survey has been prepared using the current deeds of record and does not represent a title search by this Surveyor or a guarantee of title, and is subject to any state of facts a current and accurate title search may
- 6. The recording of this plat voids, vacates and supersedes the recording of Lots 1286-1291 on the Final Plat Forrest Crossing Subdivision Section 1, Revision 10, Revision to Lots 112 & 1282—1292 Rachel Springs Business Village, as of record in Plat Book 45, Page 57, in the Register's Office for Williamson County, Tennessee.
- 7. The transfer of lots shall be subject to the provisions of the joint access easement(s), as recorded on the Final Plat of Forrest Crossing Subdivision Section 1, Revision 10, Revision to Lots 112 & 1282-1292 Rachel Springs Business Village, as of record in Plat Book 45, Page 57, in the Register's Office for Williamson County, Tennessee, and shall provide for a guaranteed, unrestricted right of access to all owners providing such easement(s) an owners of lots adjacent to such easement(s). The owners shall also be required to execute an agreement specifying responsibility for construction and perpetual maintenance of the shared

CERTIFICATE OF APPROVAL OF SUBDIVISION NAME, STREET NAMES, AND ADDRESSING

SUBDIVISON NAME AND STREET NAMES APPROVED BY THE WILLIAMSON COUNTY EMERGENCY MANAGEMENT AGENCY.

WILLIAMSON COUNTY EMERGENCY MANAGEMENT AGENCY

PARTNER

DATE

CITY OF FRANKLIN DATE

CERTIFICATE OF OWNERSHIP

- 8. Each lot will be responsible for providing detention and treatment to be designed per each Site Plan.
- 9. Each lot will be responsible for providing a 5' sidewalk in Right-of-Way designed per each individual Site Plan.
- 10. All lots shall have the right of access over and across all other lots for purposes on ingress, egress, passage and delivery by vehicles and pedestrians
- 12. These lots share a common infrastructure. As such, each lot shall be required to meet the maximum amount of caliper inches of replacement trees as calculated for that lot regardless of the amount of trees removed from
- 13. Underground Utility Note:
- Within new developments and for off-site lines constructed as a result of, or to provide service to, the new development, all utilities (including cable television, electrical, natural gas, sewer, telephone, and water lines) shall be placed underground.

ENGINEER:

DEWEY ENGINEERING

CONTACT: MICHAEL DEWEY

2925 BERRY HILL DRIVE

NASHVILLE, TENNESSEE 37204

PHONE # (615) 401-9956

mdewey@dewey-engineering.com

ITA

JAMES TERRY & ASSOCIATES

LAND SURVEYING


2603 ELM HILL PIKE, SUITE K NASHVILLE, TN 37214

PHONE (615) 490-6920

CERTIFICATE OF SURVEY

14. Proposed street lighting location, metering points and note indicating "All street light locations and quantities are approximate. Final positioning and quantities shall be at the direction of MTEMC.

- 15. Lots shall conform to all the requirements of the Franklin Zoning Ordinance.
- 16. Each lot is required to meet the minimum open space requirements, per the Franklin Zoning Ordinance, with site plan submittal.
- 17. A Streamside Buffer shall be applied to all Water Bodies serving more than twenty—five (25.0) acres of Tributary Area and Waters of the State in, or adjacent to, New Construction, Development or Redevelopment. It shall require maintenance of existing buffers on all existing properties as determined by the City Engineer and/or by the State. It shall consist of Native Vegetation along both sides of a stream or around other Water Resources or Waters of the State measured linearly perpendicular from Top of Bank that shall be determined by the break in the Slope. Final determination shall be made by the City Engineer regarding buffer delineation, Top of Bank, areas where the Streamside Buffer shall apply and buffer width requirements.
- 18. Sidewalks and trails outside of public right-of-way shall be Public Access Easements and shall be maintained by the Property Owner(s)
- 19. Cross Access Easements shall provide perpetual, non-exclusive access for the purposes of vehicular and pedestrian ingress and egress across the Cross Access Easement. Property Owner(s) shall maintain and keep the Cross Access Easement within their development in a commercially reasonable condition and state of repair.
- 20. No obstructions or encroachments which impede the flow of stormwater shall be permitted within Public Drainage Easements. The City of Franklin is not responsible for repair or replacement of any encroachments that are damaged or removed in the course of maintenance activity within easements.
- 21. Maintenance of all stormwater management features shall be the responsibility of the property owner(s) or HOA.
- 22. The City of Franklin Water Management Department has unrestricted access to its domestic water, sanitary sewer, reclaim water lines or system improvements located within its exclusive easements within the development. In the event landscaping, fencing, concrete or other structures are installed or placed within a City of Franklin easement, the City of Franklin shall have the right to remove such encroachments within the easement as may be necessary for the City of Franklin to repair, maintain or replace its infrastructure which is now or in the future may be located within the easement without obtaining any further permission from the property owner or HOA. The property owner or HOA shall be responsible for repairing and/or replacing any such landscaping, fencing, concrete or other structures removed or disturbed by the City of Franklin in common open space lots and in areas owned by the property owner or HOA at no expense to the City of Franklin, Individual homeowners shall be responsible for structures removed or disturbed by the City of Franklin within an easement on the homeowners' lot at the homeowners' expense.



LOCATION MAP NOT TO SCALE

CURVE TABLE						
CURVE NO.	DELTA	LENGTH	RADIUS	CHORD	CHD. BEARING	
C-1	17*20'21"	175.22	1149.17	346.44	S80°40'22"W	
C-2	11°49'55"	159.50	1539.24	317.30	N84°45'03"W	
C-3	09"10'29"	76.22	950.00	151.96	N83°22'58"W	
C-4	08*32'33"	71.40	956.00	142.53	S85°40'59"W	

L(LOT AREA TABLE					
LOT	ACRAGE	SQUARE FEE				
1286	2.69	117081				
1287	1.08	46866				
1288	1.51	65804				
1289	1.19	51692				
1290	1.17	50950				
1291	1.05	45815				

RIPARIAN BUFFER NOTE:

There shall be no mowing, clearing, grading, construction, storage, or disturbance of vegetation in riparian buffres except as permitted by the City Engineer, or his designee.

NOTF 'B'

Streamside Buffer Width Reductions, Clearing Activities, and Crossings

The minimum buffer width may be reduced in conjunction with targeted restoration plans that make comparable improvements to water quality. Restoration plans may include stream bank restoration, revegetation, habitat improvements, or other bioengineering methods, as approved in a Buffer Management Plan by the City Engineer. Reduction of the minimum buffer width may apply to specific areas of an overall Development, and shall be approved on a case-by-case basis. In no case shall the minimum Streamside Buffer width be less than thirty (30) feet on both sides of the stream measured from Top of Bank in limited areas. In no case shall the average minimum Streamside Buffer width of Waters of the State serving more than one (1) square mile of tributary area be less than sixty (60) feet on both sides of the stream measured from Top of Bank in limited areas.

Flood Reference

By means of graphic plotting upon Federal Emergency Management Agency Flood Insurance Rate Map (FIRM) Number: 47187C0211F, Dated: 09-29-2006, Zone: AE, and Number: 47187C0212F, Dated: 09-29-2006, Zone: AE, it has been determined that a portion of the parcels shown hereon lies within a flood hazard area.

Zoning and Setback Requirements

This property is currently zoned GO (General Office)

CERTIFICATE OF APPROVAL OF

STREETS, DRAINAGE AND SIDEWALKS

Front Yard & Street Setback: 50 Feet Side Setback: 25 Feet Rear Setback: 40 Feet

TOTAL ACRES: 8.69 ± ACRES NEW STREETS: N/A CIVIL DISTRICT: 1" = 50'

SCALE:

TOTAL LOTS: FEET NEW STREETS: N/A CLOSURE ERROR: 1:10000 DATE: SEPT. 4TH, 2018

COF PROJECT # 6796

I (WE) HEREBY CERTIFY THAT I AM (WE ARE) THE OWNER(S) OF THE PROPERTY SHOWN HEREON AS EVIDENCED IN BOOK 6446, PAGE 422, R.O.W.C., TENNESSEE, AND ADOPT THE PLAN OF SUBDIVISION OF THE PROPERTY AS SHOWN HEREON AND DEDICATE ALL PUBLIC WAYS AND EASEMENTS AS NOTED. NO LOT(S) AS SHOWN HEREON SHALL AGAIN BE SUBDIVIDED, RESUBDIVIDED, ALTERED OR CHANGED SO AS TO PRODUCE LESS AREA THAN IS HEREBY ESTABLISHED UNTIL OTHERWISE APPROVED BY THE FRANKLIN MUNICIPAL PLANNING COMMISSION, AND UNDER NO CONDITION SHALL SUCH LOT(S) BY MADE TO PRODUCE LESS AREA THAN IS PRESCRIBED BY THE RESTRICTIVE COVENANTS, AS OF RECORD IN BOOK ____,

CORRECT AND THAT ALL OF THE PAGE __, R.O.W.C., TENNESSEE, RUNNING WITH THE TITLE TO THE PROPERTY. I (WE) FURTHER CERTIFY THAT THERE ARE NO LIENS ON THE PROPERTY, EXCEPT AS FOLLOWS: BOOK ____, PAGE ___, R.O.W.C., TENNESSEE. Date Surveyor 2287 C & Y PARTNERS, LLC DATE

(WE) HEREBY CERTIFY THAT THE SUBDIVISION PLAT AS SHOWN HEREON IS MADE UNDERLAS SUPERMSTON ON THE

MONUMENTS SHOWN HEREON HAVE BEEN PLACED AS INDICATED. THE SUBDIVISION PLAT CORRECTLY REPRESENTS A SURVEY

Tenn. License No.

SEWER SYSTEMS HEREBY CERTIFY: (1) THE SEWER SYSTEMS DESIGNATED IN "RACHEL SPRINGS BUSINESS VILLAGE" HAVE BEEN NSTALLED IN ACCORDANCE WITH CITY SPECIFICATIONS, OR (2) A PERFORMANCE AGREEMENT AND SURETY IN THE AMOUNT OF \$_____ FOR THE SEWER SYSTEM HAS BEEN POSTED WITH THE

CERTIFICATE OF APPROVAL OF

CITY OF FRANKLIN, TENNESSEE, TO ASSURE COMPLETION OF SUCH SYSTEMS.

DIRECTOR SEWER DEPARTMENT

CITY OF FRANKLIN, TENNESSEE

DATE

HEREBY CERTIFY: (1) THE WATER SYSTEMS DESIGNATED IN "RACHEL SPRINGS BUSINESS VILLAGE" HAVE BEEN INSTALLED IN ACCORDANCE WITH CITY SPECIFICATIONS, OR (2) A PERFORMANCE BOND IN THE AMOUNT OF \$_____ FOR THE ON-SITE WATER SYSTEM AND \$ FOR THE OFF-SITE WATER SYSTEM HAS BEEN POSTED WITH THE MILCROFTON UTILITY

CERTIFICATE OF APPROVAL OF

WATER SYSTEMS

DATE

DISTRICT TO ASSURE COMPLETION OF SUCH SYSTEMS.

MILCROFTON UTILITY DISTRICT

I HEREBY CERTIFY: (1) THE STREETS, DRAINAGE AND SIDEWALKS DESIGNATED IN "RACHEL SPRINGS BUSINESS VILLAGE" HAVE BEEN INSTALLED WITH CITY SPECIFICATIONS, OR (2) A PERFORMANCE AGREEMENT AND SURETY IN THE AMOUNT OF \$_____ FOR STREETS, \$_____ FOR DRAINAGE, AND \$____ FOR

DIRECTOR, STREETS DEPARTMENT

CITY OF FRANKLIN, TENNESSEE

SIDEWALKS HAS BEEN POSTED WITH THE CITY OF FRANKLIN, TENNESSEE, TO ASSURE COMPLETION OF SUCH IMPROVEMENTS.

FOR RECORDING APPROVED BY THE FRANKLIN MUNICIPAL PLANNING COMMISSION, FRANKLIN, WILLIAMSON COUNTY, TENNESSEE, WITH THE EXCEPTION OF SUCH CONDITIONS, IF ANY, AS ARE NOTED IN THE PLANNING COMMISSION MINUTES FOR THE _____ DAY OF _____, 2018, AND THIS PLAT HAS OFFICE OF WILLIAMSON COUNTY, TENNESSEE.

CERTIFICATE OF APPROVAL

BEEN APPROVED FOR RECORDING IN THE REGISTER'S FRANKLIN MUNICIPAL PLANNING COMMISSION

Sheet 1 of 3

